

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
6/5/74  
JUN 5 1974  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Chief Drilling Company, Incorporated & P.S. Petroleum Company,

Complete Address 905 Century Plaza, Wichita, Kansas.

Lease Name Christine Barber Well No. 1

Location App:150' NW of SW-NE Sec. 27 Twp. 9 Rge. (E) (W) 22

County Graham Total Depth 3800'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Chief Drilling Company, Incorporated,

Address Above License No.       

Operation Completed: Hour 7:30 PM Day 3 Month 6 Year 1974

The above well was plugged as follows:

256'--8 5/8" Surface casing, cement circulated with 160 Sx.  
Top of Dakota section @ 750'.

Circulated hole with heavy mud. Pulled DP to 975' and displaced 110 Cu. Ft. cement  
thru DP from 975' to 650'. Pulled DP to 275' and displaced 30 Cu. Ft. cement thru  
DP from 275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols  
Well Plugging Supervisor

INVOICED

DATE 6/5/74

INV. NO. 9255-W