

W
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Clinton Oil Company,

Complete Address: 6810 West Highway #54, Wichita, Kansas.

Lease Name Sandlin Well No. 1-X

Location 150' NE-CNE-SW Sec. 27 Twp. 9 Rge. (E) (W) 22

County Graham Total Depth 3936

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Garvey Drilling Company,

Address: 352 North Broadway, Wichita, Kansas License No.

Operation Completed: Hour 4:30 AM Day 16 Month 2 Year 1965

The Above well, was plugged as follows:

248'--8 5/8" Surface pipe, cement circulated with 200 Sx.
Circulated hole with heavy mud, set plug @ 550' and displaced 20 Sx.
cement thru DP. Heavy mud to 240', set plug and displaced 20 Sx. cement
thru DP. Heavy mud to 40', set plug with 1/2 sack hulls and 10 Sx. cement
to bottom of cellar.

RECEIVED
STATE CORPORATION COMMISSION
2/18/65
FEB 18 1965

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *M. L. Dechle*
Well Plugging Supervisor

DATE 2/18/65
INV. NO. 900-W