

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
12/12/63
DEC 12 1963

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name The Shallow Water Refining Company.
Complete Address: 542 Petroleum Building, Wichita, Kansas.
Lease Name Sandlin Well No. 2
Location CNW-SE Sec. 27 Twp. 9 Rge. (E) (W) 22
County Graham Total Depth 3940
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated:
Plugging Contractor: Leben Drilling Inc.,
Address: 905 Central Bldg., Wichita, Kans. License No.

Operation Completed: Hour 11:30PM Day 3 Month 12 Year 1963

The Above well was plugged as follows:

207' -- 8 5/8" Surface pipe, cement circulated with 150 Sx.
Circulated hole with heavy mud, set plug @ 550' and displaced 20 Sx.
cement thru DP. Heavy mud to 180', set plug with 1/4 Sk. hulls and dis-
placed 20 Sx. cement thru DP. Heavy mud to 40', set plug with 1/2 Sx.
hulls and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 12/12/63
INV. NO. 8291-W

Signed: W. L. Nichols
Well Plugging Supervisor