

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
8/26/65
AUG 26 1965
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Petroleum, Incorporated,

Complete Address: 352 North Broadway, Wichita, Kansas.

Lease Name Blakely Well No. 1

Location App: NW-SW Sec. 30 Twp. 9 Rge. (E) (W) 22

County Graham Total Depth 3915

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Garvey Drilling Company,

Address: Route #2, Great Bend, Kansas. License No.

Operation Completed: Hour 10:00AM Day 21 Month 8 Year 1965

The Above well was plugged as follows:

226'--8 5/8" Surface pipe, cement circulated with 175 Sx.
Circulated hole with heavy mud, set plug @ 550' and displaced 20 Sx.
cement thru DP. Heavy mud to 210', set plug with 1/4 sack hulls and
displacēd 20 Sx. cement thru DP. Heavy mud to 40', set plug with 1/2
sack hulls and 10 sacks cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. D. Nichols
Well Plugging Supervisor

INVOICED
DATE 8/26/65
INV. NO. 1686-4