

¹⁶ KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
8/19/63
AUG 19 1963

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name John O. Farmer, Incorporated,

Complete Address: 370 W. Wichita, Russell, Kansas.

Lease Name Mumert Well No. 1

Location CNE-NW Sec. 30 Twp. 9 Rge. (E) (W)22

County Graham Total Depth 3880'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Forbes Casing Pulling, Incorporated,

Address: Box # 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 6:00PM Day 16 Month 8 Year 1963

The Above well was plugged as follows:

166'--8 5/8" Surface Pipe, cement circulated with 115 Sx. 3879'--4 1/2" csg.
cemented with 75 Sx. Top perforations--3808' to 3812'.

Sanded well back to 3800' and set 3 Sx cement with dump bailer. Pulled 4 1/2"
to 550' and circulated heavy gel mud, (20 sacks) and displaced 20 Sx cement
thru 4 1/2". Pulled 4 1/2" to 160' and displaced 20 Sx cement thru 4 1/2". Pulled
4 1/2" to 30' and circulated 10 Sx cement to bottom of cellar.

Recovered 3324'--4 1/2" casing.

(Mudding and cementing operations performed by Globe Cementing, Inc.)

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 8/19/63
INV. NO. 7593-W

Signed: H. D. Nichols
Well Plugging Supervisor