

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Leben Drilling, Incorporated.

Complete Address: 815 Wichita Plaza, Wichita, Kansas.

Lease Name Shutts Well No. 1

Location Appr. CSW-NW Sec. 30 Twp. 9 Rge. (E) (W) 22

County Graham Total Depth 3905

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Above

Address: License No.

Operation Completed: Hour 1:00PM Day 26 Month 6 Year 1965

The Above well was plugged as follows:

215'--8 5/8" Surface pipe, cement circulated with 175 Sx.

Circulated hole with heavy mud, set plug @ 540' and displaced 20 Sx. cement

thru DP. Heavy mud to 210', set plug with 1/2 sack hulls and displaced 20 Sx.

cement thru DP. Heavy mud to 40', set plug with 1/2 sack hulls and 10 sacks

cement to bottom of cellar.

RECEIVED
STATE CORPORATION COMMISSION
7/1/65

I hereby certify that the above well was plugged as herein stated.

INVOICED
CONSERVATION DIVISION
Wichita, Kansas

Signed: M. L. Nichols
Well Plugging Supervisor

DATE 7/1/65

INV. NO. 1394-W