

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. _____

LOCATION SW SW SE

SEC. 31 TWP. 9 RGE. 22 ✓

Dry Hole x Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Sutor

Operator K & E Drg Co Address Wichita, Kans

Field _____ County Graham

Total Depth 4113 Feet.

Plugging Contractor Barnes & Sons

Plugging Contractor's License No. 9

Address _____

(Describe briefly the manner in which the well was plugged)

8 5/8" at 224' circulated with cement - 5 1/2" at 3897' cemented

with 75 sax cement - cement to 3883' perforate at 3803'

Filled with sand to 3785', set 4 sax cement with dump bailer,

pulled 3000' 5 1/2" - pumped hole full mud (25 sax Aquagel), set

cementing plug at 220', rock and 20 sax cement, mud to 35', set

rock and 10 sax cement to bottom cellar.

Edon Lee
District Conservation Agent

Date 6-2-55

REIVED
6/6/55
JUN 6 - 1955

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 31 T 9 R 22
BOOK PAGE 124 LINE 27