

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
2/12/64
FEB 12 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Morgenstern Oil Operations,

Complete Address: 511 Union National Building, Wichita, Kansas.

Lease Name Sutor Well No. 1

Location SE-SE-NE Sec. 31 Twp. 9 Rge. (E) (W) 22

County Graham Total Depth 3870

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Company,

Address: Box # 405, Chase, Kansas License No. 436

Operation Completed: Hour 4:30PM Day 8 Month 2 Year 1964

The Above well was plugged as follows:

215'--8 5/8" Surface pipe, cement circulated. 3868'--5 1/2" Production casing
cemented with 100 Sx.
Sanded well back to 3860 and set 5 Sx. cement with dump bailer. Pulled 5 1/2"
to 660' and pumped in 5 Sx. gel, No Circulation. Pulled 5 1/2" to 570' and
pumped in 5 Sx. gel, No circulation. Pulled 5 1/2" to 480', pumped in 5 Sx.
gel, no circulation, displaced 20 Sx. cement @ 480'. Pulled 5 1/2" to 420'
pumped in 10 Sx. gel, heavy mud circulated. Pulled 5 1/2" to 190' and displa-
ced 20 Sx. cement thru 5 1/2". Pulled 5 1/2", set 5' rock bridge @ 35' and 10
Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 2/12/64
INV. NO. 8624-W

Signed: W. R. Nichols
Well Plugging Supervisor