

R

15-163 20594-00-00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JAN 5 1976

CONSERVATION DIVISION
Wichita, Kansas

1/5/76

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Dreiling Oil, Inc.

Complete Address Route #1, Box 28, Victoria, Kansas

Lease Name McMullen Well No. 1

Location NE NE SE Sec. 33 Twp. 8 Rge. (E) (W) 17

County Rooks Total Depth 3500'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Co. Tools

Address License No.

Operation Completed: Hour 4 A Day 4 Month 1 Year 1976

The above well was plugged as follows:

RTD 3500' 8 5/8 csg set 128' cwc 85 sk. Plg. Mat. 50-50 poz 2% total gel.

Gunned pits, circulated heavy mud, set 50 sk cmt plug at 550' thru drill pipe.

Heavy mud to 150' set 25 sk cmt plug thru drill pipe. Heavy mud to 40' set solid
bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 1-5-76

INV. NO. 2517-W

Signed: [Signature]
Well Plugging Supervisor