

State of Kansas



JOHN ANDERSON, Jr. Governor
 WILLIAM L. MITCHELL, Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

DEC 14 1964

12-14-64

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita 2, Kansas

Dear Sir:

Mr. Darrell Kelso of Knight Casing Pulling Co. has this

date requested permission to plug the following described well:

Morgenstern & Specter, Inc.
 Mr. Kelso guarantees payment of the plugging fee.

Operator's full Name: Morgenstern & Specter, Incorporated,Complete Address: Box # 661, Russell, Kansas,Lease Name: Desair Well No. 1Location: CSE-SE-SE Sec. 34 Twp. 9 Rgs. (E) (W) 21County Graham Total Depth 3862 Oil Well XGas Well Input Well SWD Well D & A Lost Hole Mr. Kelso was instructed to plug the well as follows:1825' -- 8 5/8" Surface pipe, cement circulated.3855 1/2' -- 5 1/2" Production casing cemented with 200 Sx.

Sand well back to 3850' and set 5 Sx. cement with dump bailer.
Pull 5 1/2" casing, bail hole to 450', set rock bridge and fill to
bottom of cellar with 5 to 1 Redi-Mix.

Very truly yours,

W. L. Deibel
 Conservation Division Agent