

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)RECEIVED
STATE CORPORATION COMMISSION

MAY 29 1974

CONSERVATION DIVISION
Wichita, KansasJ. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Marion Burris of Chief Drlg. Co., Inc., has this
date requested permission to plug the following described well:Mr. Burris guarantees payment of the plugging fee.Operator's full Name: Chief Drilling Co., Inc., and P.S. Petroleum Co.,Complete Address: 905 Century Plaza, Wichita, Kansas.Lease Name: Jeffers etal Well No. 1Location: CE/2-NW-SE Sec. 29 Twp. 9 Rge. (E)(W)22County: Graham Total Depth 3860' Oil Well Gas Well Input Well SWD Well D & A X Lost Hole Mr. Burris was instructed to plug the well as follows:200'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 825'.Circulate hole with heavy mud. Pull DP to 1050' and displace 110 Cu. Ft.
cement thru DP. Pull DP to 215' and displace 30 Cu. Ft. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to
bottom of cellar.

Very truly yours,

 Conservation Division Agent