

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
8-15-69
AUG 15 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Joe Espinosa of Braden-Deem, Incorporated, has this date requested permission to plug the following described well:

Mr. Espinosa guarantees payment of the plugging fee.

Operator's full Name: George Ablah,

Complete Address: 8028 Cork, Wichita, Kansas.

Lease Name: Van Loenen Well No. A-1

Location: NE-NE-NE Sec. 10 Twp. 9 Rge. (E)(W)22

County: Graham Total Depth 3875' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Espinosa was instructed to plug the well as follows:

208'--8 5/8" surface casing, cement circulated with---
Top of Dakota section @ 700'.
3869'--5 1/2" casing cemented on bottom with 125 Sx. No plug back indicated,
Top perforations from 3500' to 3503'.

Push plug to 3475' set sand bridge and 5 Sx. cement with dump bailer.
Pull 5 1/2" casing and squeeze well with 5 sacks hulls, 30 sacks gel and
130 Sx. cement, staged.

Very truly yours,

M. L. Deibel
Conservation Division Agent