

State of Kansas



## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)RECEIVED  
STATE CORPORATION COMMISSION  
10-4-71  
OCT 4 1971  
CONSERVATION DIVISION  
Wichita, KansasJ. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Johnny Crowe of Garvey Drilling Company has this  
date requested permission to plug the following described well:Mr. Crowe guarantees payment of the plugging fee.Operator's full Name: Petroleum, Incorporated.Complete Address: 300 West Douglas, Wichita, Kansas.Lease Name: Van Loenen Well No. B-1Location: App: NE-SE Sec. 10 Twp. 9 Rge. (E)(W) 22County: Graham Total Depth 3560' Oil Well Gas Well  Input Well  SWD Well  D & A X Lost Hole Mr. Crowe was instructed to plug the well as follows:205'---8 5/8" Surface casing, cement circulated with 175 Sx.  
Top of Dakota section @ 725'.Circulate hole with heavy mud. Pull DP to 950' and displace 100' Sx.  
cement thru DP. Pull DP to 215' and displace 20 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

Very truly yours,

Conservation Division Agent