

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
OCT 5 1966
10-5-66
CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Claude Norwood of Leben Drilling, Inc., has this date requested permission to plug the following described well:

Mr. Norwood guarantees payment of the plugging fee.

Operator's full Name: Aspen Drilling Company & Dean & Clark

Complete Address: Box # 783, Great Bend, Kansas.

Lease Name: Manaugh Well No. 2

Location: 150' West of CNE-NW Sec. 29 Twp. 9 Rge. (E)(W) 22

County Graham Total Depth 3890 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Norwood was instructed to plug the well as follows:

224' -- 8 5/8" Surface pipe, cement circulated with 170 Sx.

Circulate hole with heavy mud, set plug @ 540' and 20 Sx. cement.

"	"	210' with 1/4 sk. hulls &
"	"	20 Sx. cement.
"	"	40 With 1/2 sk. hulls &
"	"	10 Sx. cement.

Very truly yours,

H. L. Nichols

Conservation Division Agent