

State of Kansas



WM. H. AVERY Governor
 WILLIAM L. MITCHELL Chairman
 JAMES O. GREENLEAF Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

JUN 12 1967

6-12-67

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita 2, Kansas

Dear Sir:

Mr. Albert Unruh of Southwest Csg. Pulling Co has this date requested permission to plug the following described well:

Mr. Unruh guarantees payment of the plugging fee.

Operator's full Name: Aspen Drilling Company,

Complete Address: Box # 783, Great Bend, Kansas.

Lease Name: Manauh Well No. A-1

Location: CSW-SW Sec. 29 Twp. 9 Rge. (E)(W) 22

County Graham Total Depth 3852 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Unruh was instructed to plug the well as follows:

206'--8 5/8" Surface pipe, cement circulated with 200 Sx.
3851'--5 1/2" Production casing cemented with 120 Sx. Top per-
forations from 3777' to 3782'.

Sand well back to 3750' and set 5 Sx. cement with dump bailer.

Pull 5 1/2" casing and squeeze hole with 20 Sx. gel using 5 Sx.

hulls in initial gel and follow with 75 Sx. cement.

Very truly yours,

M. S. Nichols
 Conservation Division Agent