

State of Kansas



JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building  
WICHITA, KANSAS 67202

RECEIVED  
STATE CORPORATION COMMISSION

OCT 07 1982 10/7/82

CONSERVATION DIVISION  
Wichita, Kansas

VERBAL PERMIT FORM  
(To be filed by Plugging Agent)

Lost Circulation

Dear Sir:

Mr. Gene Brown of Gene Brown Oil has this  
date requested permission to plug the following described well:

Operator's Full Name: Gene Brown

Complete Address: 407 South Main, Plamville, Kans. 67663

Lease Name: Rues Well No. #1-H" (SWD)

Location: 75' F.E.L. - 890' F.S.L. Sec. 31 Twp. 8<sup>S</sup> Rge. 17<sup>W</sup> (E) (W)

County: Rooks Total Depth: 1627 FE

Abandoned Oil Well ☐ Gas Well ☐ Input Well ☐ SWD Well ☒ D&A ☐

Other well as hereafter indicated: Lost Circulation - Abandoned and Plugged.

Mr. Brown was instructed to plug the well as follows:

8 5/8" 179 FE SP. CUM By Halliburton Ont.

Lost Circulation @ 1627 FE (Note Report Attached)

Order 310 50 50 Forming 4% Gel. 3% Cal. Cl. and 8 5/8" Plug  
spot with Drill Stem - With heavy mud between all Plugs.

1<sup>st</sup> Plug @ 1380 FE w/ 100<sup>st</sup> Ont

2<sup>nd</sup> Plug @ 1210 FE w/ 50<sup>st</sup> Ont.

3<sup>rd</sup> Plug @ 660 FE w/ 100<sup>st</sup> Ont.

4<sup>th</sup> Plug @ 270 FE w/ 40<sup>st</sup> Ont

5<sup>th</sup> Plug solid Budge @ 40 FE to 0 w/ 10<sup>st</sup> Ont.

10<sup>st</sup> In Bat Hole (CIRCULATE)

Conservation Division Agent

Note (Report Attached)

(By Halliburton)

M. J. Smith