

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

Form CB-3
Rev. 6-68
7/21/80
RECEIVED
STATE CORPORATION COMMISSION
JUL 21 1980
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 143-19031-00-00 (of this well) N.A.

Operator's Full Name HENNY BROWN ENTERPRISES
Complete Address DRAWER 340 PLAINVILLE, KANS. 67663
Lease Name DOPITA Well No. "A" #3
Location C-N¹/₂-N¹/₂-SE Sec. 31 Twp. 8^S Rge. 19 (E) (W) W
County ROOKS Total Depth 3378 FE
Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____
Other well as hereafter indicated _____
Plugging Contractor HALLIBURTON CEMENTING CO.
Address 1100 EAST 8TH ST. HAYS, KANS. License No. _____
Operation Completed: Hour 12:15 PM Day 16TH Month JULY Year 1980

The above well was plugged as follows:

8 5/8" 158 FE SP. CUR. → 5 1/2" SET AT 3378 FE → PLUG BACK T.D. 3350 FE
PERF'S - 3090-95 → 3190-93 → 3269-73 → 3284-89 → 3309-12 → 3330-32
CASING PARTED AT 2400 FE ABANDONED WELL - NO PIPE RECOVERY.
ORDERED 285ST HALLIBURTON LIGHT AND 10ST HULL'S
PUMPED IN WITH PUMP TRUCK.
PUT IN 3ST HULL'S AND 265ST CMT. WITH 6ST HULL'S MIXED IN.
PUT 25ST CMT. AND 1ST HULL'S IN ANNULUS. → MAX PRESSURE 200 LBS
RETURNED ON JULY 18TH 80 → PUMPED IN TOP 30ST CMT. → CASING FULL
TO CELLAR.

I hereby certify that the above well was plugged as herein stated (CEMENTED BY HALLIBURTON)

INVOICED
DATE 7-25-80
INV. NO. 2684-6

Signed: Maureen Schmitt
Well Plugging Supervisor