

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
APR 26 1976
APR 26 1976

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Reiter of Murfin Drlg. has this

date requested permission to plug the following described well:

Mr. Reiter guarantees payment of the plugging fee.

Operator's full Name: Murfin Drlg. Co.

Complete Address: 617 Union Center, Wichita, Ks.

Lease Name: Richard "D" Well No. 1

Location: 1320 FSL & 990' FWL NE/4 Sec. 23 Twp. 8 Rge. (E)(W) 18

County: Rooks Total Depth 3431' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Reiter was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set 70 sk cmt plug at 535' thru drill

pipe. Heavy mud to 160' set 20 sk cmt plug thru drill pipe. Heavy

mud to 40' set solid bridge & 10 sk cmt plug to base of cellar.

Very truly yours,

R. W. Massey
Conservation Division Agent