

15-163-03022-00-00

4-060669

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- - 6-28-42

C NW NE /4 SEC. 31, 08 S, 17 W
4620 feet from S section line
1980 feet from E section line

Operator license# 4074

Lease Iruss well # 1

Operator: Innes Petroleum, Inc.
Ron Innes

County Rooks

Address: 229 East William
O'Rourke Title Building
Wichita, Kansas 67202

Well total depth 3389 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 1284 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Northwest Well Service License#

Address: Hill City, Kansas 67642

Company to plug at: Hour: 9:00A.M. Day: 5 Month: April Year: 95

Plugging proposal received from: Mike Vanausdale

Company: Northwest Well Service Phone: 913-674-2852

Were: Order 325 sxs. 60/40 posmix - 10% gel and hulls.
Well open to TD - pulled tubing and rods on April 4, 1995 -
good condition. Emergency permission to plug the well. F.L. 1300' from
surface.

Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 11:30A.M., Day: 5, Month: April, Year: 95

Actual plugging report: 8 5/8" to 1284'. 5 1/2" to 3380'. Dug out
wellhead and found cement in braden head. Perforated well at 825' -
1325' and 1730'. Tied onto production casing and pumped 325 sxs. cement
with 250# hulls. Max. P.S.I. 1300#. S.I.P. 400#.

RECEIVED
KANSAS CORPORATION COMMISSION

APR 25 1995
4/25/95

Remarks: Halliburton Cementing.
Condition of casing(in hole): GOOD X BAD Any plug: YES X NO
Bottom plug(in place): YES , CALC X, NO Dakota plug: YES X, NO
Plugged through TUBING , CASING X. Elevation: 1921 GL

I did[X] / did not[] observe the plugging.

(agent)