

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 8/19/63
 AUG 19 1963

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

CONSERVATION DIVISION
 Wichita, Kansas

Dear Sir:

Mr. Albert Schiffner of Forbes Casing Pulling Inc., has this

date requested permission to plug the following described well:

John O. Farmer, Inc.,

Mr. Schiffner guarantees payment of the plugging fee.

Operator's full Name: John O. Farmer, Incorporated,

Complete Address: 370 W. Wichita, Russell, Kansas.

Lease Name: Mumert Well No. 1

Location: CNE-NW Sec. 30 Twp. 9 Rge. (E) (W) 22

County Graham Total Depth 3880' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Schiffner was instructed to plug the well as follows:

166'--8 5/8" Surface pipe, cement circulated. 3879'--4 1/2" casing
cemented with 75 Sx. Perforated from 3808' to 3812'.

Sand well back to 3800' and set 3 Sx cement with Dump bailer.

Pull 4 1/2" to 550', circulate heavy mud and displace 20 Sx cement

thru 4 1/2" .. Pull 4 1/2" to 160' and displace 20 Sx. cement thru 4 1/2".
Pull 4 1/2", set bridge @ 35' and 10 Sx cement to bottom of cellar.

Very truly yours,

W. L. Nichols
 Conservation Division Agent