

State of Kansas

FORM - CP-2
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
2/12/64
FEB 12 1964

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Glenn Hall of Knight Casing Pulling Co. has this

date requested permission to plug the following described well:
Morgenstern Oil Operations,

Mr. Hall guarantees payment of the plugging fee.

Operator's full Name: Morgenstern Oil Operations,

Complete Address: 511 Union National Building, Wichita, Kansas.

Lease Name: Sutor Well No. 1

Location: SE-SE-NE Sec. 31 Twp. 9 Rge. (E) (W) 22

County Graham Total Depth 3870 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Hall was instructed to plug the well as follows:

215'--8 5/8" Surface pipe, cement circulated. 3868'--5 1/2" pro-
duction casing cemented with 100 Sx.
Sand well back to 3860' and set 5 Sx. cement with dump bailer.
Pull 5 1/2" to 600' and circulate heavy gel mud. Pull 5 1/2" to 540'
and displace 20 Sx. cement thru 5 1/2". Pull 5 1/2" to 200' and displace
20 Sx. cement thru 5 1/2". Pull 5 1/2", set 5' rock bridge @ 35' and 10
Sx. cement to bottom of cellar.

Very truly yours,

W. R. Nichols