

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

6/18/63
 JUN 18 1963

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

CONSERVATION DIVISION
 Wichita, Kansas

Dear Sir:

Mr. A. G. Radke of Garver Drilling Co. has this

date requested permission to plug the following described well:
Petroleum Inc.

Mr. Radke guarantees payment of the plugging fee.

Operator's full Name: Petroleum Incorporated,

Complete Address: 352 North Broadway, Wichita, Kansas.

Lease Name: Sutor Well No. G-1

Location: SE-SE Sec. 31 Twp. 9 Rge. (E) (W) 22

County Graham Total Depth 3840 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Radke was instructed to plug the well as follows:

240'--8 5/8" Surface casing, cement circulated with 150 Sx.

Circulate hole with heavy mud, set plug @ 540' and 20 Sx cement.

" " 230' with 1/4 Sk hulls & 20 Sx cement.
" " 40' with 1/2 Sk hulls & 10 Sx cement.

Very truly yours,

H. L. Nichols
 Conservation Division Agent