

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
CONSERVATION DIVISION

DEC 5 1966
DEC 5, 1966
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. McCluskey of Cities Service has this
date requested permission to plug the following described well:

Mr. McCluskey guarantees payment of the plugging fee.

Operator's full Name: Cities Service Oil Company

Complete Address: Box 553 Russell, Kansas

Lease Name: McMillen "B" Well No. 5

Location: C SE SW NE Sec. 25 Twp. 8 Rge. 18 (E) (W) X

County Rooks Total Depth 3460' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. McCluskey was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 540' and displace
25 sc cement thru drill pipe. Heavy mud to 230' set cementing plug and displace
20 sc cement thru drill pipe. Heavy mud to 40' set cementing plug, 1/2
sc hulls and 8 sc cement to base of cellar. Plug rat hole with 2 sc cem.

Very truly yours,

Geo. M. [Signature]
Conservation Division Agent