



15-163-21278-00-00

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

Dear Sir:

Mr. Tom Casey of Frontier Oil has this date requested permission to plug the following described well:

Operator's Full Name: Frontier Oil Co

Complete Address: 1720 KSB Bldg. Wichita, Kansas.

Lease Name: Lourey Well No. 1

Location: NE-SW-NE Sec. 33 Twp. 8 Rge. 19 (E) (W)

County: Roos Total Depth: 3436

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Casey was instructed to plug the well as follows:

8 5/8" @ 243' w/170 sv - 4 1/2" @ 3434 w/200 sv
Sand to 3375' + dump 4 sv cmt. - Recovered 2100'
Ordered 140 sv 50/50 permix 6% gel. 3% cc. -
22 gel. - 6 hulls + 8 5/8" plug - Pumped in 5 hulls =
14 gel → 1 hull → 70 cmt → 8 gel → Rel. Plug → 70
cmt Max PSI 500# Shut in 250#

Very truly yours,

RECEIVED
STATE CORPORATION COMMISSION
AUG 09 1982
CONSERVATION DIVISION
Wichita, Kansas

Dennis L. Hamel
Conservation Division Agent