



15-163-21466-00-02

JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building  
WICHITA, KANSAS 67202

### VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Terry Pisker of Frontier Oil Co. has this date requested permission to plug the following described well:

Operator's Full Name: Frontier Oil Co

Complete Address: 1720 KSBVT Bldg. Wichita, Kansas 67202

Lease Name: Carrow Well No. J-2WD

Location: Rooks SE-SF-SW Sec. 33 Twp. 8 Rge. 19 (E) (W)

County: Rooks Total Depth: 680'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereafter indicated: attemp to drill SWD - hit metal

Mr. Pisker was instructed to plug the well as follows:

8 5/8" set @ 1440' - old plug @ 3531-3450 w/25 sk, - mud 3450-1440 - cmt @ 1440-1362 w/25 sk, - mud 1362-250 - cmt @ 250' to 172 w/25 sks, - mud 172-84 - cmt. at 84-60 w/25 sk - drilled to 680' hit metal & abandon.

Ordered 250 sk 5/8" pozmix - 6% gel + 3% CA-11-10 sk gel & 3 hulls.

Pumped in through 3" tubing @ 671' 70 sk cmt & 2 hulls -> losing fluid -> 9 gels & 1 hull -> fluid static -> 70 cmt -> pulled 9 points -> circ gel to surf w/85 sk -> pulled 13 hulls & filled to top w/ 10 sks - cmt fluid static at top of 8 5/8"

Very truly yours, (cmt by other)

Dennis L. Hamel  
Conservation Division Agent

RECEIVED

11/27/82