

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JOHN C. WOELK Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

SEP 7 1965
Sep 7 1965
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Dwight Dellenger of Knight Casing Pulbing Co has this

date requested permission to plug the following described well:

Morrison Producing Co.

Mr. Dellenger guarantees payment of the plugging fee.

Operator's full Name: Morrison Producing Company,

Complete Address: 400 North Main, Box #712, Eldorado, Kansas.

Lease Name: Kuehn1 (WASHDOWN) Well No. 1

Location: CSE-NW-SW Sec. 33 Twp. 8 Rge. (E)(W) 21

County Graham Total Depth 3684 Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Dellenger was instructed to plug the well as follows:

190'--13 3/8" surface pipe, cement circulated. Surface pipe filled with cement from former plugging job. Drilled 7 7/8" hole thru surface. 3680'--5 1/2" Production casing cemented with 175 Sx. Top perforations from 3393' to 3395'.

Sand well back to 3380' and set 5 Sx. cement with dump bailer. Pull 5 1/2" to 600' and circulate heavy gel mud. Pull 5 1/2" to 540' and displace 20 Sx. cement thru 5 1/2". Pull 5 1/2" to 210' and displace 25 Sx. cement thru 5 1/2". Pull 5 1/2", set bridge @ 35' and 15 Sx. cement to bottom of cell.

Very truly yours,
H. L. Nichols
Conservation Division Agent