

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JAN 15 1970
CONSERVATION DIVISION
Wichita, Kansas
JAN 15 1970

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Delbert Adams of Forbes Casing Pulling Co., Inc has this
date requested permission to plug the following described well:

Mr. Adams guarantees payment of the plugging fee.

Operator's full Name: Bulldog Pipe & Supply Company,

Complete Address: 612 Mayo Building Tulsa, Oklahoma 74103

Lease Name: Sanford Well No. 1

Location: NE-NE-NW Sec. 5 Twp. 8 Rge. (E)(W) 22

County: Graham Total Depth 3780' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Adams was instructed to plug the well as follows:

203'--8 5/8" Surface casing, cement circulated with 175 Sx.
3640'--5 1/2" Production casing cemented on bottom with 150 Sx. Top of
cement @ 2820' (Temp. Survey). Well Plugged back to 3449'. Top per-
forations from 3390' to 3394'. Well has been squeezed from Dakota to
surface with cement. No attempt to recover 5 1/2" casing.

Squeeze well with 1 sack hulls, 30 sacks gel and 70 Sx. cement, staged.

Very truly yours,

[Signature]
Conservation Division Agent