

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION
JAN 15 1970
CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Delbert Adams of Forbes Casing Pulling Co. Inc. has this date requested permission to plug the following described well:

Mr. Adams guarantees payment of the plugging fee.

Operator's full Name: Bulldog Pipe & Supply Company

Complete Address: 612 Mayo Bldg., Tulsa, Oklahoma 74103

Lease Name: Sanford Well No. 2

Location: SW-NE-NW Sec. 5 Twp. 8 Rge. (E)(W) 22

County: Graham Total Depth 3792 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Adams was instructed to plug the well as follows:

223'--8 5/8" Surface casing, cement circulated with 175 Sx.
3791'--5 1/2" Production casing cemented on bottom with 140 Sx. Well
plugged back to 3559'. Top perforations from 3554' to 3549'.

Sand well back to 3525' and set 5 Sx. cement with dump bailer. Pull 5 1/2"
casing and squeeze well with 5 sacks hills, 25 sacks gel and 130 Sx.
cement, staged.

Very truly yours,

Conservation Division Agent