



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JAN 15 1970 JAN 15, 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Delbert Adams of Forbes Casing Pulling Co., Inc. has this
date requested permission to plug the following described well:

Mr. Adams guarantees payment of the plugging fee.

Operator's full Name: Bulldog Pipe & Supply

Complete Address: 612 Mayo Bldg., Tulsa, Oklahoma 74103

Lease Name: Sanford Well No. 3

Location: NE-NW-NW Sec. 5 Twp. 8 Rge. (E)(W) 22

County: Graham Total Depth 3812' Oil Well

Gas Well Input Well SWD Well X D & A Lost Hole

Mr. Adams was instructed to plug the well as follows:

207'--8 5/8" Surface casing, cement circulated with 150 Sx.
3654'--5 1/2" casing cemented on bottom with 125 Sx. Well plugged back to
3400'. Top perforations @ 3331'.

Push plug to 3325', sand to 3300' and set 5 Sx. cement with dump bailer.
Pull 5 1/2" casing and squeeze well with 5 sacks hulls, 35 sacks gel and
130 Sx. cement, staged.

Very truly yours,

M. L. Nichols
Conservation Division Agent