

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-077-21604-00-00
Spot: NWNW Sec/Twnshp/Rge: 15-31S-7W
625 feet from N Section Line, 945 feet from W Section Line
Lease Name: DRUMWRIGHT Well #: 1-15
County: HARPER Total Vertical Depth: 4783 feet

Operator License No.: 3581
Op Name: RED OAK ENERGY, INC.
Address: 7701 E KELLOGG DR STE 710 PO BOX
WICHITA, KS 67207

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	212	0	

155.45

Well Type: DP DH KCCPKT UIC Docket No: _____ Date/Time to Plug: 01/02/2008 3:00 AM
Plug Co. License No.: 5822 Plug Co. Name: VAL ENERGY, INC.
Proposal Rcvd. from: GREG DAVIDSON Company: VAL ENERGY, INC. Phone: (316) 263-6688

Proposed Plugging Method: Fill hole with heavy mud & spot cement through drill pipe. Spot 35 sxs. cement @ 1,250', 35 sxs. cement @ 850', 35 sxs. cement @ 270', 25 sxs. cement @ 60', 15 sxs. cement in rat hole, & 10 sxs. cement in mouse hole.

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: NONE
Date/Time Plugging Completed: 01/02/2008 7:15 AM KCC Agent: MICHAEL WILSON

Actual Plugging Report:

Perfs:

Filled hole with heavy mud & spotted cement through drill pipe. Spotted 35 sxs. cement @ 1,250', 35 sxs. cement @ 850', 35 sxs. cement @ 270', 25 sxs. cement @ 60', 15 sxs. cement in rat hole, & 10 sxs. cement in mouse hole.

INVOICED
DATE 1-16-08
INV. NO. 2008061071

RECEIVED
KANSAS CORPORATION COMMISSION
JAN 10 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POSMIX W/4% GEL BY ALLIED CEMENTING. INVOICE #41353.

Plugged through: DP

District: 02

Signed Michael Wilson
(TECHNICIAN)

PKT