

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-23971-00-01
Spot: SWNE Sec/Twnshp/Rge: 6-20S-21W
920 feet from N Section Line, 920 feet from E Section Line
Lease Name: SCHABEN P Well #: 1 TWIN
County: NESS Total Vertical Depth: 4403 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: 8100 E 22ND ST N # 700 BOX 783188
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
PC		1444		WITH 215 SX CMT
PROD	5.5	4388	0	WITH 115 SX CMT
SURF	8.625	336		WITH 180 SX CMT

143.10

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/19/2007 10:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: BENNIE DILLS Company: RITCHIE EXPLORATION Phone: (316) 691-9500

Proposed Plugging Method: RUN TBG TO BOTTOM AND PUMP 50 SX CMT & 200# HULLS. PULL TBG TO 1500' & CIRCULATE CMT TO SURFACE. PULL TBG & TOP OFF WITH CMT. TIE ONTO BACKSIDE & PUMP CMT IF POSSIBLE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/19/2007 4:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN TUBING TO 4350' & PUMP 50 SX CMT & 200# HULLS. 1ST PLUG PULL TBG TO 1500' & PUMP 165 SX CMT. CIRCULATED TO SURFACE. 2ND PLUG PULL TBG & TOP OFF WITH 25 SX CMT. TIED ONTO BACKSIDE & PUMP 25 SX CMT. PRESSURE TO 500# & HELD.

Perfs:

Top	Bot	Thru	Comments
4388	4403		OPEN HOLE


INVOICED

DATE 1-16-08
INV. NO. 2008061072

Remarks: USED60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01



RECEIVED
KANSAS CORPORATION COMMISSION

JAN 11 2008 Form CP-2/3

CONSERVATION DIVISION
WICHITA, KS

PKT