

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

OR

FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging of formations.

Graham County. Sec. 35 Twp. 9 Rge. ~~XXV~~ 21 (W)

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines. NEc. NE SW

Lease Owner M. B. Armer

Lease Name DeYoung Well No. 1

Office Address 306 Insurance Bldg., Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed June 2 1949

Application for plugging filed June 2 1949

Application for plugging approved June 2 1949

Plugging commenced June 2 1949

Plugging completed June 2 1949

Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
<u>Kansas City</u>	<u>dry</u>	<u>3570</u>	<u>3784</u>			
<u>Arbuckle</u>	<u>dry</u>	<u>3922</u>	<u>3960</u>	<u>8-5/8"</u>	<u>155'</u>	<u>none</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud and set bottom plug at 155', cemented with 10 sacks cement - filled surface pipe with mud to top plug set at 25' with 15 sacks of cement.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to M. B. Armer

Address 306 Insurance Bldg., Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, SS. M. B. Armer

(Employee of Owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) M. B. Armer

306 Insurance Bldg., Wichita 2, Kansas

SUBSCRIBED AND SWORN to before me this 4th day of June, 1949.

My commission expires Sept. 17, 1951

Hazel Walton
Notary Public.



Company: M. B. Armer
Contractor: Armer Drilling Company, Inc.
Drilling Commenced: 5/20/49
Drilling Completed: 6/3/49
Elevation: 2317 D.F.
Rig #1 - rotary

Farm: DeYoung #1
Location: NE NE SW 35-9-21
Graham County, Kansas
Casing record: 8-5/8" @ 155'
cemented w/75 sacks

(figures below indicate bottom)

Sand	90
Shale & shells	800
Sand	960
Shale & sand	1165
Sand	1510
Shale	1535
Shale & lime	1760
Anhydrite	1795
Shale & lime	2320
Broken lime	2420
Shale & lime	2515
Lime	2555
Lime & shale	2645
Lime	2705
Lime & shale	3605
Lime	3708
Lime & shale	3855
Conglomerate	3922
Dolomite - rotary total depth	3960 D & A

Formation Tops:

Heebner	3528
Lansing	3570
Base Kansas City	3784
Conglomerate	3855
Arbuckle	3922

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

ARMER DRILLING COMPANY, INC.

By

M.B. Armer

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

JUN - 4 1949
STATE CORPORATION
COMMISSION

Subscribed and sworn to before me, a notary public, in and for said County and State this 4th day of June, 1949.

Hazel Walton
Notary Public

My commission expires Sept. 17, 1951

