

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Graham County, Sec. 35 Twp. 9 Rge. 21 (E) W (W)

Location as "NE/CNW/SW" or footage from lines NW SW NW

Lease Owner H. B. Mabee Company

Lease Name DeYoung Well No. 1

Office Address Box 94718, Oklahoma City, Oklahoma 73109

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 4-22 19 70

Application for plugging filed 4-22 19 70

Application for plugging approved 4-22 19 70


Plugging commenced 4-22 19 70

Plugging completed 4-22 19 70

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well W. L. Nichols

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Pipe				8 5/8"	195'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

- 1st. plug was set @ 1050' with 70 sacks cement
- 2nd. plug was set @ 215' with 20 sacks cement
- 3rd. plug was set @ 40' with 10 sacks cement
- Cementing to bottom of cellar

RECEIVED
STATE CORPORATION COMMISSION
APR 28 1970
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor L. J. Dreiling & Sons, Inc.

Address Route 2, Victoria, Kansas 67671

STATE OF KANSAS, COUNTY OF ELLIS, ss.
I, Leo F. Dreiling (employee of owner) or (CONSULTANT) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leo F. Dreiling

LEO F. DREILING, ROUTE 2, VICTORIA, KANSAS 67671


(Address)

SUBSCRIBED AND SWORN to before me this 27th day of April, 19 70

My commission expires September 19, 1970

Joseph A. Hess
JOSEPH A. HESS

Notary Public.



L. J. DREILING AND SONS, INC.

15-065-20322-00-00

Victoria, Kansas 67671

WELL LOG

Company	H. B. Mabee Company Box 94718 Oklahoma City, Oklahoma 73109	Sec. 35	Twp. 9	Rng. 21
Farm	DeYoung No. 1	Location	NW SW NW	
Total Depth	3920'	County	Graham	
Comm.	4-16-70 Comp. 4-22-70	Elevation:	2307'	K. B.
Contractor	L. J. Dreiling & Sons, Inc. Victoria, Kansas 67671 Casing Record Cement Record		2304'	D. F.
			2302'	G. R.
		Production:	D & A	
	195' - 8 5/8"		135 sacks cement	

Figures Indicate Bottom of Formations

0'	134'	Top Soil & Sand
134'	270'	Shale
270'	1135'	Shale & Sand
1135'	1270'	Shale
1270'	1500'	Sand
1500'	1761'	Redbed
1761'	1800'	Anhy.
1800'	2440'	Shale
2440'	3642'	Shale & Lime
3642'	3904'	Lime
3904'	3920'	Arbuckle
3920'	T.D.	

RECEIVED
STATE CORPORATION COMMISSION
APR 28 1970
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
)ss
COUNTY OF ELLIS)

I, Leo F. Dreiling, of the L. J. Dreiling & Sons, Inc., upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report from your DeYoung #1.

Leo F. Dreiling

LEO F. DREILING

Subscribed and sworn to before me this 27th day of April 1970.

JOSEPH A. HESS
NOTARY PUBLIC
COUNTY OF ELLIS, KANSAS

Joseph A. Hess

JOSEPH A. HESS NOTARY PUBLIC

My commission expires: September 19, 1970