

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Graham County. Sec. 14 Twp. 9S Rge. 22W (E) (W)

Location as "NE/CNW/SW" or footage from lines C-SE-SE-NW

Lease Owner Sunray Mid-Continent Oil Company

Lease Name Sandzen Well No. 1

Office Address Box # 788, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed March 27, 1956

Application for plugging filed April 18, 1956

Application for plugging approved April 19, 1956

Plugging commenced April 26, 1956

Plugging completed April 28, 1956

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well 3875 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	233'	None
				5 1/2"	3852'	3211'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with sand to 3660', ran 4 sacks cement to 3630'. Mudded hole to 220', set 10' rock bridge, ran 15 sacks cement to 155'. Mudded hole to 35', set 10' rock bridge, ran 10 sacks cement to base of cellar. Plugging completed

RECEIVED
STATE CORPORATION COMMISSION
MAY 31 1956
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Company
Address Chase, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
Norman E. Montgomery (employee of owner) or (owner/representative) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Norman E. Montgomery
Box # 788, Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 4 day of May, 19 56

My commission expires Dec. 24, 1956 Notary Public.

PLUGGING
FILE SEC 14 T 9 R 22W
BOOK PAGE 54 LINE 41

WELL LOG

15-065-03492-00-00

COMPANY **Sunray-Midcontinent Oil Company**

SEC. **14** T. **9** R. **22**


FARM **Sandson** NO. **1**

LOC. **SE SE NW**

TOTAL DEPTH **3855'**

COUNTY **Graham Co., Kansas**

COMM. **March 11, 1956** COMP. **March 21, 1956**



CONTRACTOR **GARVEY DRILLING COMPANY**

CASING **8-5/8" @ 233' w/250 sacks**
5-1/2" @ 3852' w/125 sacks

ELEVATION **2292 D.F.**

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

40	Clay & Shale
235	Shale
1730	Sand, Shale & Shells
1800	Shale & Shells
1840	Anhydrite
2020	Shale & Shells
3560	Lime & Shale
3855	Lime
3855	T.D.

STATE OF KANSAS
DIVISION OF OIL AND GEOL
GEOLOGICAL SURVEY
COMMISSIONER
1956

State of KANSAS }
County of SEDWICK } SS:

PLUGGING
FILE SEC 14 T 9 R 22W
BOOK PAGE 54 LINE 41

I, Carl Hurty of GARVEY DRILLING COMPANY
upon oath state that the above and foregoing is a true and correct copy of the log of the #1 Sandson well

Carl Hurty

Subscribed and sworn to before me this 29th day of March 19 56

My Commission Expires: September 2, 1959

Frances Sloan
NOTARY PUBLIC

FRANCES SLOAN, Notary Public
My Commission expires Sept. 2, 1959