


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

Graham County. Sec. 14 Twp. 9S Rge. 22W ~~(E)XXXXXX(W)~~  
Location as "NE/CNW%SW%" or footage from lines SE NE SW  
Lease Owner PRODUCERS OIL COMPANY  
Lease Name Sandzen B Well No. 2  
Office Address 711 Philtower Building, Tulsa, Oklahoma  
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well  
Date well completed April 19 56  
Application for plugging filed October 19 67  
Application for plugging approved Renewed 2/23 19 68  
Plugging commenced 2/24 19 68  
Plugging completed 2/26 19 68  
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production Feb. 19 68  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols  
Producing formation Kansas City Depth to top 3857 Bottom            Total Depth of Well 3863 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Kansas City Lime	Oil	3560	3579	5-1/2	3859	999.28
				8-5/8	216	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from            feet to            feet for each plug set.  
Pushed plug to 3550'. Filled hole with sand to 3500'. Mixed and ran 5 sacks cement through dump bailer.  
Mixed and pumped 35 sacks fel with 5 sacks hulls followed with 130 sacks of cement.

RECEIVED  
STATE CORPORATION COMMISSION  
3/21/68  
MAR 21 1968  
CONSERVATION DIVISION  
Wichita, Kansas

Name of Plugging Contractor Allied Cementing Company (If additional description is necessary, use BACK of this sheet)  
Address Russell, Kansas

STATE OF OKLAHOMA, COUNTY OF TULSA, ss.  
R. E. COUCH (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
711 Philtower Building, Tulsa, Oklahoma  
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of March, 19 68

My commission expires 7/1/71  
Charlotte Lucas Notary Public.

15-065-01522-00-00

CENTURY PRODUCTION CO. - K & E DRILLING, INC.  
Sandzen No. 2

SE NE SW Sec. 14-9S-22W  
Graham County, Kansas

Comm: April 4, 1956  
Comp: April 15, 1956  
Total Depth: 3863'

RECEIVED  
STATE CORPORATION COMMISSION

OCT 27 1961

CONSERVATION DIVISION  
Wichita, Kansas

Casing

Cement

8 5/8" Set @ 216'  
5 1/2" Set @ 3859'

140 sacks  
150 sacks

FORMATION

DEPTH

Clay	0 - 30
Sand	30 - 60
Shale & clay	60 - 216
Shale	216 - 800
Sand & shale	800 - 1210
Shale	1210 - 1355
Sand	1355 - 1545
Red Bed - shale	1545 - 1814
Anhydrite	1814 - 1845
Shale shells	1845 - 2200
Lime & shale	2200 - 3565
Lime	3565 - 3733
Lime & shale	3733 - 3810
Lime	3810 - 3863

3859  
35  

---

24

STATE OF KANSAS )  
                          ) SS  
SEDGWICK COUNTY )

I hereby certify that the above information is true and correct to the best of my knowledge.

*Dale Silcott*

Subscribed and sworn to before me this 19th day of April, 1956

*Francis Mader*  
Notary Public

My commission Expires: June 25, 1956