

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

15-065-03000-00-00

API NUMBER Completed 5-8-56

LEASE NAME Sandzen

WELL NUMBER 2

1,650 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 14 TWP. 9 RGE. 22 (X) or (W)

COUNTY Graham

Date Well Completed 5-8-56

Plugging Commenced 7-10-95

Plugging Completed 7-12-95

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Four-Way Operating, Inc.

ADDRESS Box 698, Great Bend, Kansas 67530

PHONE# (316-792-2506) OPERATORS LICENSE NO. 5310

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on June 23, 1995 (date)

by Dennis Hamel (KCC District Agent's Name).

Is ACO-1 filed? NA If not, is well log attached? Filed with CP-1

Producing Formation Lansing-KC Depth to Top 3519' Bottom T.D. 3850

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	200'	None
				5-1/2"	3849'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Perforated 4 shots at 1820' and at 1050'. Ran 2-1/2" tubing to 1900'. Pumped 150 sack 40/60 pozmix cement with 10% added gel and 350# hulls down tubing, circulated to surface. Pulled tubing. Pumped 50 sacks cement down 5-1/2" casing at 400 psi and 50 sacks cement in annulus.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: _____

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (Employee of Operator) (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) James W. Rockhold

(Address) Box 698, Gt. Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 24 day of July, 1995

Iona M. Leatherman
 Notary Public

My Commission Expires _____



RECEIVED
 STATE CORPORATION COMMISSION
 7/28/95
 JUL 28 1995