


OR
FORMATION PLUGGING RECORD

Strike out upper line when reporting plugging off formations.

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Graham County. Sec. 14 Twp. 9S Rge. (E) 22 (W)

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE/4
Lease Owner Phillips Petroleum Company
Lease Name Sandzen Well No. 1
Office Address Bartlesville, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed August 10, 1944 19
Application for plugging filed August 11, 1944 19
Application for plugging approved August 11, 1944 19
Plugging commenced August 11, 1944 19
Plugging completed August 12, 1944 19
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Arbuckle Depth to top 3955 Bottom 3985 Total Depth of Well 3985 Feet

Show depth and thickness of all water, oil and gas formations.

CASING RECORD

OIL, GAS OR WATER RECORDS

Formation	Content	From	To	Size	Put In	Pulled Out
Topeka Lime	Dry	3274				
Heavener	Dry	3484				
Lansing Kansas City	Dry	3515				
Conglomerate	Dry	3884				
Arbuckle	Dry	3955				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud to 245' ran wood plug at 245' with 30 sacks cement through open end drill pipe, filled hole with mud to 25', ran 10 sacks of cement in filling to the base of the cellar. Cement pumped in well by H alliburton Oil Well Cementing Company.

PLUGGING
MUD 14 9 22W
WOOD 128 13

8/16/44

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Ralph McKnight
Address Box 528 - Russell, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.
Ralph McKnight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Ralph McKnight*
Box 528 - Russell, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 14th day of August, 1944

My commission expires June 14, 1948
My commission expires
Robert J. Mason Notary Public.

Formation Record

Lease Sandzen

Well No. 1

FROM	TO	Formation	REMARKS
0	760	Shale & Sand	<u>Elevation 2299' D.F.</u>
760	1125	Shale, Shells & Sand	
1125	1140	Sand	
1140	1530	Shale & Shells	
1530	1780	Shale & Red Bed	
1780	1855	Anhydrite	
1855	2156	Shale & Shells	
2156	2400	Lime	
2400	2455	Lime & Shale	
2455	2820	Lime	
2820	2960	Lime & Shale	
2960	3040	Lime	
3040	3322	Lime & Shale	Top Topeka 3274'-no shows. Top Heavener 3484'-no shows. Top LKC 3515'-no shows. Soft from 3618 to 3624-with slight stain.
3630	3669	Lime & Chert	Soft from 3632' to 3636' -with no saturation
3669	3745	Lime	
3745	3843	Conglomerate	
3843	3985	Lime	Top Conglomerate 3884'-no shows. Top Arbuckle 3955'-no shows.

3529
2299
2156

14 9 22W
128 13

AUG 16 1915