

STATE OF KANSAS
CORPORATION COMMISSION


WELL PLUGGING RECORD

Give all Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Graham County, Sec. 10 Twp 9S Rge 22 (W)

Location as "NE/CNW/SW" or footage from lines S/W S/W S/W
Lease Owner Wolfson Oil Co et al
Lease Name J. C. Swayze Well No. 1
Office Address Box 1144, Wichita Falls,
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 7-4-50 19
Application for plugging filed 7-17-51 19
Application for plugging approved 7-17-51 19
Plugging commenced 7-30-51 19
Plugging completed 8-5-51 19
Reason for abandonment of well or producing formation Well went to water

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production April 20, 1951 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty, Hays, Kansas
Producing formation 3912-28' Depth to top 3912 Bottom 3928 Total Depth of Well 3928 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Anhydrite & Shale		1650	1840	8-5/8"	1840'	None
Heebner Shale		3521	3550			
Toronto		3553	3556			
Lansing		3566	3575			
Arbuckle		3912	3928	5-1/2"	3913'	2136'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pumped plug to 3910' and dumped in 5 Sax of cement. Shot casing off at 2136'. Filled hole with heavy mud to 250'. Set permanent rock bridge. Dumped 15 Sax of cement-filled hole with mud to 30' of top. Mixed 10 Sax cement for Cap on Well.

RECEIVED
AUG 17 1951

Name of Plugging Contractor J. O. Forbes
Address Great Bend, Kansas

STATE OF TEXAS, COUNTY OF WICHITA, ss.
Sam Wolfson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Sam Wolfson
P.O. Box 1144, Wichita Falls, Texas
(Address)

SUBSCRIBED AND SWORN to before me this 13th day of August 19 51



(Signature) O.H. Coats
Notary Public.

My commission expires 6-30-53

23-8390-s 6-51-20M

8-14-51

PLUGGING
FILE NO. 10-19-224
BOOK PAGE 94 LINE 34

KANSAS WELL LOG BUREAU --- KANSAS GEOLOGICAL SOCIETY
 412 UNION NATIONAL BANK BUILDING - WICHITA, KANSAS

COMPANY Wolfson Oil Company


SEC. 10 T. 9S R. 22W
 LOC. S/W S/W S/W

FARM J. C. Swayze NO. 1

TOTAL DEPTH 3928'

COUNTY Graham

COMM. COMP.
 SHOT OR TREATED Acidized with 500 7-1-50
 CONTRACTOR Herndon Drilling Co
 ISSUED for Gulf Oil Corporation



CASING

20	10	
15½	8¼	1840'
12½	6¾	
13¾	5¼	3913'

ELEVATION 2300'

PRODUCTION None

FIGURES INDICATE BOTTOM OF FORMATIONS

	From	To
Surface clay & sand	0'	70'
Shale		365'
Shale & sand		610'
Shale & shells		845'
Shale		1000'
Sand, shale & shells		1650'
Red rock & shale		1832'
Anhydrite & shale		1842'
Shale		2065'
Shale & shells		2210'
Shale & lime		2390'
Lime & shale		3020'
Lime		3025'
Lime & shale		3510'
Lime		3865'
Lime & shale		3928'

TOTAL DEPTH

ED:RL
 8-25-50

RECEIVED
 STATE COMMISSION
 AUG 17 1951

RECEIVED
 STATE COMMISSION

PLUGGING
 FILE SEC 10 T 9 R 22W
 BOOK PAGE 94 LINE 34