

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Graham County. Sec. 29 Twp. 9S Rge. 22W (E) (W)

Location as "NE/CNW/SW" or footage from lines 150' West of C NE NW

Lease Owner Aspen Drilling Company

Lease Name Manaugh Well No. 2

Office Address P. O. Box 783, Great Bend, Kansas 67530

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 10-1-66 1966

Application for plugging filed 10-1-66 1966

Application for plugging approved 10-1-66 1966


Plugging commenced 10-1-66 1966

Plugging completed 10-1-66 1966

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above
Section Plat

Name of Conservation Agent who supervised plugging of this well W. L. Nichols, Moreland, Kansas

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3890 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	224'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set Plug @ 540' with 20 sacks cement
Set Plug @ 210' with 20 sacks cement
Bridged plug @ 40' with 1/2 sk. hulls and 10 sacks cement

RECEIVED
STATE CORPORATION COMMISSION

OCT 6 1966

10-6-66
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.
Address Box 486, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.
Leslie Kite (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leslie Kite

P. O. Box 486, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of October, 1966

My commission expires Oct 19, 1968

Emma Maiten Bennett
Notary Public.

DRILLER'S LOG

COMPANY: Aspen Drilling Company
 CONTRACTOR: LEBEN DRILLING, INC.
 FARM: MANAUGH #2
 LOCATION: 150' WEST OF C NE NW
 GRAHAM COUNTY, KANSAS
 COMMENCED: 9-24-66
 COMPLETED: 10-1-66

0	110	Shale, Post Rock
110	330	Shale
330	1475	Shale, Sand
1475	1930	Shale, Redbed
1930	1968	Anhydrite
1968	2175	Shale
2175	2300	Shale, Shells
2300	2420	Lime, Shale
2420	2985	Shale, Lime
2985	3550	Lime, Shale
3550	3620	Shale, Lime
3620	3660	Lime, Shale
3660	3890	Lime
	<u>3890</u>	<u>RTD - D. & A.</u>

RECORDED
 OCT 6 1966
 CONSERVATION DIVISION
 Wichita, Kansas

8 5/8" used surface casing set @ 224' cemented with 170 sacks of Common with 2% cc

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Manaugh #2 Well, located 150' West of C NE NW of Section 29, Township 9 South, Range 22 West, Graham County, Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite
 Leslie Kite

STATE OF KANSAS)
) SS
 COUNTY OF BARTON)

Subscribed and sworn to and before me, a Notary Public, in and for Barton County, Kansas, this 5th day of October, 1966.

James Walter Bensch

My Commission Expires:
October 19, 1968