

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-163-20-628 0000

LEASE NAME DOPITA A

WELL NUMBER A-8

1320 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 31 TWP. 8 RGE. 17 (E) or (W)

COUNTY ROOKS

Date Well Completed 8-23-1976

Plugging Commenced 3-31-1998

Plugging Completed 3-31-1998

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR KENNY BROWN ENTERPRISES, LLC

ADDRESS P.O. BOX 277 Hays, Kansas 67601-0277

PHONE# (785) 628-3384 OPERATORS LICENSE NO. 32250

Character of Well _____

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 3-31-1998 (date)

by Herb Deines (KCC District Agent's Name).

Is ACO-1 filed? unknown If not, is well log attached? _____

Producing Formation arbuckle & Kansas City Depth to Top 3121' Bottom 3416' T.O. 3442'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

| Formation | Content | From | To | Size | Put in | Pulled out |
|-----------|------------|------|------|-------|--------|------------|
| | surface | top | 158 | 8 5/8 | 158' | |
| | production | top | 3441 | 5 1/2 | 3431' | |
| | tubing | | | 2 7/8 | 3441' | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from ___ feet to ___ feet each section.
Run tubing in hole. Perforated casing @ 1750' & 1320'
Tubing set @ 1730' spotted 100 sacks & 400 lbs. hulls.
Pulled up to 900' pumped 90 sacks & 300lbs. hulls. Cement circulated.
Tied on to annulus. pumped 30 sacks & 100 lbs. hulls. Top off casing 10 sacks.

Name of Plugging Contractor HALLIBURTON SERVICE License No. _____

Address HAYS, KANSAS

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: KENNY BROWN ENTERPRISES, LLC

STATE OF KANSAS COUNTY OF ELLIS, ss.

Steve Ruder operator/member (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed in the same are true and correct, so help me God.

(Signature) Steve Ruder

(Address) Box 277 Hays, KS

SUBSCRIBED AND SWORN TO before me this 1st day of April, 19 98



Denise E. Whisman
Notary Public

My Commission Expires: Nov. 25, 2001

USE ONLY ONE SIDE OF EACH FORM

CHANNEL MASTER
BASE 407

Kenny Brown Equip. 15-163-20628-00-00
DOPITA A #A-8

KING OIL Co

DOPITA A-8

2800

TOP ALL cement