

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

15-163-19034-00-01

API NUMBER 040918

LEASE NAME Russ

WELL NUMBER # 3

4400 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 30 TWP. 8S RGE. 17 (E) or (W)

COUNTY Rooks

Date Well Completed 8/7/64

Plugging Commenced 7 July 1988

Plugging Completed 7 July 1988

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Kinderhook Oil & Gas, Inc.

ADDRESS R.R. #2, Box 906, Waukee, IA 50263

PHONE# (515) 271-2821 OPERATORS LICENSE NO. 6585

Character of Well abandoned oil producer

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 7 July 1988 (date)

by Dennis L. Hamel (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? it is

Producing Formation Kansas City Depth to Top 3123 Bottom 4110

PB to 3304 RECEIVED 10
 STATE CORPORATION COMMISSION

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

DEC 2 1988

Formation	Content	From	To	Size	Put In	Pulled out
Kansas City	oil & water	surface	210	8 5/8	unknown	CONSERVATION DIVISION Wichita, Kansas
Arbuckel	Oil & water	surface	3410	5 1/2		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Original perfs 3219-21 + 3293-95 on 7 July perferd at 1325' (3 holes), 750' (holes), and 200' (3 holes). Pumped in 25 sks cement w/ 1 1/4 lb F.C. followed by 250 sks cement w/ 6 sks hulls mixed in next 60 bbl cement slurry. Max pressure 500 lb. S.T.P. 300 lb. Pumped 25 sks cement w 1 1/4 lb F.C. in 8 5/8 at max pressure of 500 lb.
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co. License No. _____

Address P. O. Box 31, Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Kinderhook Oil & Gas, Inc.


STATE OF Iowa COUNTY OF Polk, ss.

James L. Christiansen, Pres., Kinderhook Oil & Gas, Inc. (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James L. Christiansen Pres.

(Address) James L. Christiansen, Pres.
 Kinderhook Oil & Gas, Inc.

R.R. 2, Box 906, Waukee, IA 50263



SUBSCRIBED AND SWORN TO before me this 30th day of November, 19 88

Wanda J. Swanson
 Notary Public

My Commission Expires: 15 August 1990