


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

15-143-00761-0000

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Rooks _____ County. Sec. 33 Twp. 8 Rge. 17 (E) X (W)
Location as "NE/CNW/SW" or footage from lines. SE SE SE
Lease Owner Burch Drilling Co., Inc.
Lease Name McMullen Well No. 1
Office Address 1011 Union Center
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed 7-28-58 19_____
Application for plugging filed 7-28-58 19_____
Application for plugging approved 7-28-58 19_____
Plugging commenced 7-28-58 19_____
Plugging completed 7-28-58 19_____
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production _____ 19_____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3510 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				85/8"	170'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set 1st plug @ 600' w/20 sx.
Set 2nd plug @ 170' w/15 sx.
Set 3rd plug @ 40' w/10 sx.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Burch Drilling Co., Inc.
Address 1011 Union Center, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Earl M. Burch (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Earl M Burch

SUBSCRIBED AND SWORN TO before me this 5th day of August, 1958

My commission expires July 27, 1960

Gunny Harrison
Notary Public.

PLUGGING
FILE SEC. 33 T. 8 R. 17 W.
BOOK PAGE 120 LINE 7

8/7/58

15-163-00761-00-00

WELL LOG

Burch Drilling Company, Inc.
#1 McMullen
SE SE SE 33-8S-17W
Rooks County, Kansas

8 5/8" set @ 170' w/125sx/
Elevation: 2031 KB
Comm: 7-22-58
Comp: 7-28-58
D & A

250	Shale & Sand	Anhydrite	Tops: 1356'
1215	Shale	Heebner	3148'
1356	Shale & Shells	Toronto	3171'
1395	Anhydrite	Lansing	3191'
1550	Shale		
1910	Shale & Lime Streaks	DST #1 3312'-3360'. Open 1 hr. Rec.	
3150	Shale & Lime	16' Mud with few specks oil. IBHP (30	
3482	Lime	mins.) missed, IFP 0#, FFP 0#, FBHP	
3510	Cherty Lime	(30 mins.) 540#.	
3510	RFD		

STATE OF KANSAS, COUNTY OF SEDGWICK:

I, Earl M. Burch, president of Burch Drilling Co., Inc. being duly sworn on oath, state: That I have knowledge of the facts, statements and matters herein contained and that the same are true and correct.

Earl M. Burch
Earl M. Burch

Subscribed and sworn to before me this 5th day of August, 1958.

Garry Harrison
Notary Public

My commission expires: July 27, 1960.

8/7/58
PLUGGING
FILE SEC. 33 T. 8 R. 17W
BOOK PAGE 120 LINE 7