

15-163-02655-00-00  
WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Rocks \_\_\_\_\_ County. Sec. 35 Twp. 8 Rge. 17 (E) (W)

Location as "NE/CNW/SW" or footage from lines C SE NE SW

Lease Owner Bennett & Roberts Oil Operations

Lease Name Hindman Well No. #2

Office Address Russell, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed April 12, 19 63

Application for plugging filed July 5, 19 63

Application for plugging approved July 7, 19 63


Plugging commenced July 8, 19 63

Plugging completed July 11, 19 63

Reason for abandonment of well or producing formation Not enough oil to produce economically

If a producing well is abandoned, date of last production None 19   

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Lansing Depth to top 3103 Bottom 3346 Total Depth of Well 3390 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	237	None
				5 1/2	3389 1/2	2558

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged back w/crushed rock @ 3060\* & dumped  
5 sxs. cement - Filled to 3030\* plug @ 550\*  
Pumped 15 sxs gel mud & 20 sxs cement - Plug  
@ 200\* - Pumped 20 sxs cement - Bridge hole  
@ 30\* pumped 10 sxs cement to base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION

JUL 19 1963

CONSERVATION DIVISION  
Wichita, Kansas

7/19/63

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Glenn & Smith Pipe Pulling Co.

Address Ellinwood, Kansas

STATE OF KANSAS, COUNTY OF RUSSELL, ss.

Jack Haynes (employee of owner) or ~~(owner)~~ of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jack Haynes

Russell, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 16 day of July, 1963

My commission expires May 7, 1964

Mildred Carr  
Notary Public.



Bennett & Roberts Oil Operations  
HINDMAN #2

SE NE SW Sec. 35-8-17W  
Rooks County, Kansas

R.T.D. 3390\*

CONTRACTOR: Bennett & Roberts Drilling, Inc.

Commenced 3/25/63  
Completed 4/1/63

Sec 8 5/8" @ 237' w/160 sax cml.  
Sec 5 1/2" @ 331' w/ 200 sax cml.

15-163-02655-00-00

Surface Clay & Post Rock	40'
Shale & Shells	553
Sand	580
Shale	655
Sand	685
Shale	830
Sand	915
Red Bed	1274
Anhydrite	1305
Shale & Shells	1949
Shale & Lime	2430
Shale	2435
Shale & Shells	2550
Shale & Broken Lime	2718
Shale w/Lime streaks	2829
Shale & Lime	3044
Lime	3135
Lime & Shale	3171
Lime	3209
Lime & Shale	3390

**RECEIVED**  
STATE CORPORATION COMMISSION

JUL 8 1963

CONSERVATION DIVISION  
Wichita, Kansas

7/8/63

STATE OF KANSAS)  
RUSSELL COUNTY ) SS.

I hereby certify that the above information is correct to the best of my knowledge.

BENNETT & ROBERTS DRILLING, INC.

By W. Robert L. Pothoff

Subscribed and sworn to before me this 5th day of April, 1963.

My Commission Expires 6/17/66

W. Robert L. Pothoff  
Notary Public