

15-163-00562-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 6-15-1953

LEASE NAME Hazen

WELL NUMBER 1

NE NE NW 1 Ft. from S Section Line

1 Ft. from E Section Line

SEC. 25 TWP. 8 RGE. 18 (E) or (W)

COUNTY Rooks

Date Well Completed 6-15-1953

Plugging Commenced 12-5-89

Plugging Completed 1-10-90

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Okmar Oil Company

ADDRESS Box 723 Hays, Kansas 67601

PHONE#(913) 628 6101 OPERATORS LICENSE NO. 5245

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12-5-89 (date)

by Dennis Hamel (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 3426

PBTD 2371

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	Surface	0	95	8 5/8		--
	Casing	0	3411	5 1/2		--

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet, each set.
Run tubing to 2282'. Rig up BJ Titan and pump 100 sks. 65/35 8% gel 1/4# flowseal with 200# hulls. Pull tubing to 1256'. Pump 120 sks. 65/35 10% gel with 250# hulls. Pull tubing and hook up to casing. Pump 30 sks. 65/35 10% gel. Pressure to 300#. Shut in at 250#. Hook up to annulus pump 15 sks. 65/35 10% gel. Cement coming out of cellar. Dug casing down 15' cut hole in surface casing. Cement between surface and long string.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Okmar Oil Company License No. 5245

Address Box 723 Hays, Kansas 67601 (BJ Titan cementer)

STATE OF Kansas COUNTY OF Ellis, ss.

Mr. Ted Crawford

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts stated, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) Ted Crawford

(Address) Box 723 Hays, Ks 67601

ROSEMARY SMITH
NOTARY PUBLIC
STATE OF KANSAS
MY ABPT. EXP. MAY 5, 1991
SUBSCRIBED AND SWORN

to before me this 15 day of January, 19 90

Rosemary Smith
Notary Public

My Commission Expires: 5/1/1991

JAN 10 1990
COMMISSION
WICHITA, KS 67202