


15-163-02440-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

Rooks County. Sec. 25 Twp. 8 Rge. (E) 18 (W)  
Location as "NE/CNW/SW" or footage from lines 330' E, 990' S, N 1/4 corner  
Lease Owner Cities Service Oil Co.  
Lease Name McMillen "B" Well No. 3  
Office Address Bartlesville, Oklahoma  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 10-20-54 19  
Application for plugging filed 10-20-54 19  
Application for plugging approved 10-21-54 19  
Plugging commenced 10-21-54 19  
Plugging completed 10-21-54 19  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production - 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty  
Producing formation Arbuckle Depth to top 3460' Bottom - Total Depth of Well 3512' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	240'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from - feet to - feet for each plug set.

Fill with heavy mud to 230', set wood plug, 1/2 sx Hulls, 15 sx cement, heavy mud to 40', 1/2 sx Hulls, 10 sx cement to surface.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Lohmann-Johnson  
Address Evansville, Indiana

STATE OF Kansas, COUNTY OF Barton, ss.  
James Porter (employee of owner) or ~~(owner or possessor)~~

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) James Porter

Box 553, Russell, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 1st day of November, 1954

My commission expires Nov 17, 1955

W. B. Smith  
Notary Public.



NOV-2, 1954

# WELL RECORD

Company Cities Service Oil Co. Well No. 3 Farm McMillen "B"  
 Location 790' South and 330' East of N/4 Cor. Sec. 25 T. 8 R. 18W  
 Elevation 2004 (2002 Cr.) County Neosho State Kansas  
 Drlg. Comm. October 12, 1954 Contractor Lehmann-Johnson Drlg. Co., Inc.  
 Drlg. Comp. October 21, 1954 Acid None  
 T. D. 3512' Initial Prod. Dry Hole - P. & I. 10-21-54

CASING RECORD:

8-5/8" x 240' cas. 175 wt cement

FORMATION RECORD:

shale	0-530
sand & shale	875
sand	985
shale & sand streaks	1308
anhydrite	1347
shale & shells	1950
shale & lime	2230
lime & shale	2605
shale & lime	2730
lime & shale	3260
lime	3305
lime & shale	3428
lime, shale & chert	3470
lime	3512 T. D.

Rechner	3122'
Dodge	3147'
Lanning	3166'
Base Kansas City	3377'
Conglomerate	3426'
Evos. Arkuckle	3427'
Arkuckle	3460'
Penetration	52'
Total depth	3512'

D. S. T. 3167-83, open 30 mins., recovered 5' mud with few specks oil; B. H. P. 110#/30 mins.

D. S. T. 3317-46, open 1 hr., recovered 82' muddy water with few specks oil; B. H. P. 1000#/30 mins.

SYFO: 500' 0"  
 1000' 1"  
 1500' 0"  
 2000' 0"  
 2500' 0"  
 3050' 0"

7-7/8" rotary hole.

*Received*

NOV-2, 1954

**PLUGGING**  
 FILE NO. 25-8-18W  
 DATE 72 TIME 42