


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Rooks County, Sec 25 Twp. 8 Rge. (E) 18 (W)
Location as "NE/CNW 1/4 SW 1/4" or footage from lines 330 W 990 S of Center
Lease Owner Cities Service Oil Co.
Lease Name Tanzey Well No. 1
Office Address Bartlesville, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed 7/26 19.49
Application for plugging filed 7/26 19.49
Application for plugging approved 7/26 19.49
Plugging commenced 7/26 19.49
Plugging completed 7/26 19.49
Reason for abandonment of well or producing formation Dry



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19...
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Arbuckle Lime Depth to top 3460 Bottom Total Depth of Well 3500 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Arbuckle Lime	Dry			8-5/8	300	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from... feet to... feet for each plug set.

Filled with heavy mud from total depth 3500 feet to 295 feet set wood plug, dumped 15 sacks cement, mud to 35 feet set plug, dumped 10 sacks cement, mud and dirt to surface.

RECEIVED
AUG 27 1949
ST. JOHNS
COMMISSION

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to...
Address...

STATE OF KANSAS, COUNTY OF Barton, ss.
Mr. James Porter (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James Porter
Box 553, Russell, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 75th day of August 1949
W. D. Smith

My commission expires 3-17-1951

Notary Public.

PLUGGING
FILE SEC 25 T 8 R 18W
BOOK PAGE 107 LINE 19

WELL RECORD

Company Citizen Service Oil Co. Well No. 1 Farm Yanney
 Location 990' South and 330' West of Center Sec. 25 T. 8 R. 18W
 Elevation 2013 (2011 Gr.) County Hooks State Kansas
 Drlg. Comm. July 16, 1949 Contractor Holsa Drilling Company
 Drlg. Comp. July 26, 1949 Acid None
 T. D. 3500' Initial Prod. None - Dry Hole (P. & A. 7-27-49)

GRADING RECORD:

3-5/8" @ 300' cen. 175 oz cement

FORMATION RECORD:

lime	0-90
shale & shells	590
sand & shale	725
sand	775
shale, shells & sand	1100
shale, red bed & sand	1345
anhydrite	1405
shale & shells	1635
shale & salt	1800
shale & shells	2000
lime & shale	2160
shale & lime	2610
shale & shells	2770
lime & shale	2915
shale & lime	3025
lime & shale	3045
lime	3472
lime & chert	3500 T. D.

Top Topeka	2932'
Top Lansing	3178'
Top Conglomerate	3419'
Top Kros. Artuckle	3460'
Penetration	40'
Total Depth	3500'

SYFO:	500'	10
	1000'	00
	1500'	00
	2000'	00
	2500'	10
	3000'	10

PLUGGING
 FILE SEC 25 T. 8 R. 18W
 BOOK PAGE 107 LINE 19

RECEIVED
 Conservation Div.
 AUG 27 1949
 AUG 27 1949
 STATE CORPORATION
 COMMISSION
 KANSAS