

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD

Rooks County, Sec. 25 Twp. 8 Rge. 18 (E) (W)

Location as "NE/CNW/SW" or footage from lines SE SW NW

Lease Owner Harry Gore

Lease Name Hazen Well No. 1

Office Address 400 Brown Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) oil

Date well completed 3-3-49

Application for plugging filed 11-22-55

Application for plugging approved 11-22-55

Plugging commenced 11-12-55

Plugging completed 11-20-55

Reason for abandonment of well or producing formation oil exhausted

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes-verbal

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well 3417 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	195	
				5-1/2	3429	2411

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

3421 to 3410 ft. Sand bridge
 3410 to 3390 5 sks. cement
 3390 to 300 Mudded
 300 to 285 Rock bridge
 285 to 240 15 sks. cement
 240 to 35 Mud
 35 to Cellar 10 sks. cement

DEC 6 1955
 DEC 6 - 1955
 CONSERVATION DIVISION
 Wichita, Kansas

Name of Plugging Contractor R & S Pipe Pulling Co.
Address Box 192, Ellinwood, Kansas

STATE OF Kansas COUNTY OF Sedgwick ss. Theodore Gore

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Theodore Gore
400 Brown Bldg., Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of December, 19 55

My commission expires June 7, 1956
Charlotte Ketchka Notary Public.

PLUGGING
 FILE NO. 25-8-18W
 BOOK PAGE 18 LINE 40

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - HARRY GORE
Farm - Hazen

No. 1

SEC. 25 T. 8 R. 18W
SE SW NW

Total Depth. 3423'

Comm. 2-17-49

Comp. 3-3-49


Shot or Treated.

Contractor.

Issued. 6-4-49

County. Rocks

KANSAS



Elevation. _____

Production. 45 bbls.

Figures Indicate Bottom of Formations.

surface soil	40
sand & shale	100
shale & shells	195
shale	225
shale & shells	870
shale & sand	1015
shale & shells	1245
red bed & shale	1315
anhydrite	1358
shale & shells	1885
shale & lime	3265
lime	3420
arbuckle	3423
Total Depth	

Tops:
Arbuckle 3417
(From Rig Floor:)

6-4-49
DEC 6 - 1955
CONSERVATION
WICHITA, KANSAS

PLUGGING
FILE SEC 25 T. 8 R. 18W
BOOK PAGE 18 LINE 40