

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Oil Producers of Kansas, Inc.
Address: 1710 Waterfront Parkway, Wichita, KS 67201
Phone: (316) 681-0231 Operator License #: 8061
Type of Well: Oil, Gas Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) *(If SWD or ENHR)*
The plugging proposal was approved on: _____ (Date)
by: Steve Durrant (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 081-21221 - 00-00
Lease Name: Hoffman
Well Number: 2-223
Spot Location (QQQQ): NW NW-NE
330 Feet from North / South Section Line
2310 Feet from East / West Section Line
Sec. 23 Twp. 30 S. R. 34 East West
County: Haskell
Date Well Completed: 12-17-98
Plugging Commenced: 12-17-07
Plugging Completed: 12-18-07

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	1680	
				4 1/2	5598	1780

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Pumped bottom, had 150 psi max, shut in 50 psi, dug cellar and pit, unpacked casing head, set floor, pulled slips, cut surface off 4' below ground, checked bottom, cement at 4350', had 17" stretch, ripped casing at 2240', worked pipe, ripped casing at 2010', worked pipe, ripped casing at 1780', pipe came free, pumped 15 gel, 50 sacks cement, pulled to 800', pumped 50 sacks cement, pulled to 40', pumped 20 sacks, emptied pit, cleaned up location.

RECEIVED
KANSAS CORPORATION COMMISSION

Name of Plugging Contractor: Quality Well Service, Inc. License #: 31925

Address: 190 US Highway 56, Ellinwood, KS 67526

JAN 02 2008


Name of Party Responsible for Plugging Fees: Oil Producers of Kansas, Inc.

CONSERVATION DIVISION
WICHITA, KS

State of Kansas County, Sedgwick, ss.

Oil Producers Inc. of Kansas

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) [Signature]
(Address) 1710 Waterfront Parkway, Wichita KS 67206

SUBSCRIBED and SWORN TO before me this 31st day of December, 2007

Lorie A. Zehr My Commission Expires: May 5, 2010
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

[Handwritten initials]