

**KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING APPLICATION**  
Please TYPE Form and File ONE Copy

Form CP-1  
September 2003  
This Form must be Typed  
Form must be Signed  
All blanks must be Filled

API # 15-175-21, 193-00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date N/A

Well Operator: McCoy Petroleum Corp. KCC License #: 5003  
(Owner / Company Name) (Operator's)

Address: P.O. Box 39 City: Spivey

State: Kansas Zip Code: 67142 Contact Phone: (620) 532-9232

Lease: Rooney C Well #: 1-18 Sec. 18 Twp. 31 S. R. 34  East  West

C - SW - NW Spot Location / QQQQ County: Seward

3300 Feet (in exact footage) From  North /  South (from nearest outside section corner) Line of Section (Not Lease Line)

4620 Feet (in exact footage) From  East /  West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One:  Oil Well  Gas Well  D&A  Cathodic  Water Supply Well  
 SWD Docket # \_\_\_\_\_  ENHR Docket # \_\_\_\_\_  Other: \_\_\_\_\_

Conductor Casing Size: \_\_\_\_\_ Set at: \_\_\_\_\_ Cemented with: \_\_\_\_\_ Sacks

Surface Casing Size: 8 5/8" Set at: 1754' Cemented with: 400 Sacks

Production Casing Size: 5 1/2" 15.5# Set at: 5798' Cemented with: 275 Sacks

List (ALL) Perforations and Bridgeplug Sets: Upper Morrow Sand perms 5326' - 5329'

DV Tool @ 3206' with 225 sx. TOC @ 2200' bottom 50 sks 200# HULLS TD 4900.

Elevation: (  G.L. /  K.B. ) T.D.: 5800' PBTD: 5753' Anhydrite Depth: \_\_\_\_\_  
(Stone Corral Formation)

Condition of Well:  Good  Poor  Casing Leak  Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): as per KCC Pipe recovery 2050.

1st plug @ 1800' @ 15 sx gel, 50 sx crt. 2nd plug @ 900' @ 50 sx  
3rd plug @ 40' @ 20 sx

Is Well Log attached to this application as required?  Yes  No Is ACO-1 filed?  Yes  No

If not explain why? \_\_\_\_\_

**RECEIVED**  
KANSAS CORPORATION COMMISSION

**JAN 04 2008**

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission, KS

List Name of Company Representative authorized to be in charge of plugging operations: Dave Oller

Phone: (620) 532-9232

Address: P.O. Box 39 City / State: Spivey, KS 67142

Plugging Contractor: Quality Well Service KCC License #: 31925  
(Company Name) (Contractor's)

Address: 190th U.S. 56 Highway Ellinwood, KS 67526 Phone: (620) 727-3410

Proposed Date and Hour of Plugging (if known?): ASAP 2/19/07

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 11-26-07 Authorized Operator / Agent: Brent B Reinhardt  
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

629-7125

5753  
5300  
453

well plugged - KCC-DIG Dist 01