

Correction

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-19203-00-01
Spot: S2NENW Sec/Twnshp/Rge: 12-30S-5E
4332 feet from S Section Line, 3316 feet from E Section Line
Lease Name: HOWARD Well #: 2B
County: COWLEY Total Vertical Depth: 2869 feet

Operator License No.: 5556
Op Name: VIVA INTERNATIONAL, INC.
Address: 8357 MELROSE DR
LENEXA, KS 66214

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF		91		

93.24

Well Type: EOR UIC Docket No: E04611.1 Date/Time to Plug: 11/26/2007 8:00 AM
Plug Co. License No.: 5870 Plug Co. Name: PHILLIPS WELL SERVICE, INC.
Proposal Rcvd. from: FRED STACKLEY Company: CONTRACT PUMPER Phone: (316) 368-6704

Proposed Plugging Method: SAND BACK @2790', & 5 SXS, OR CIBP AND 25 SXS, PULL CASING, 250' TO SURFACE.

Plugging Proposal Received By: WitnessType: NONE
Date/Time Plugging Completed: 11/26/2007 12:00 AM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

Perfs:

RUN IN HOLE W/TBG @ 2802', CONSOLIDATED CEMENTING DUMPED W/WATER 300# OF 20/40 SAND, AND MIXED & PUMPED 15 SXS 60/40 POZMIX 4% GEL 3% CC. PERFORATED 5-1/2" CSG @ 250', RIH W/TBG @250', CONSOLIDATED CEMENTING MIXED & PUMPED 170 SXS 60/40 POZMIX 4% GEL TO SURFACE. SWEDGED INTO 5-1/2" CSG AND PUMPED 15 SXS TO SURFACE. CEMENT CIRCULATED, PLUG DOWN 1700 PM 11-26-2007. CONSOLIDATED CEMENTING TICKET #12910.

INVOICED
DATE 1-4-08
INV. NO. 2008061020

Remarks: E-04611, -096.83541,37.45943, OPEN HOLE 2816'-2869'

Plugged through: TBG

RECEIVED
KANSAS CORPORATION COMMISSION

JAN 09 2008

CONSERVATION DIVISION
WICHITA, KS

District: 02

Signed

Duane Krueger
(TECHNICIAN)

AKT